

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pratt County, Sec. 17 Twp. 27S Rge. 14W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

SW NE NE

Lease Owner Beren Corporation  
Lease Name Schaefer #1 Well No. 1  
Office Address 970 Fourth Financial Center, Wichita, Ks 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Dry Hole


Date Well completed December 13, 1979 19  
Application for plugging filed December 13, 1979 19  
Application for plugging approved December 13, 1979 19  
Plugging commenced 10:30 AM December 13, 1979 19  
Plugging completed 12:45 PM December 13, 1979 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4560'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	378'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.  
Spot 50 sacks at 600' through open end  
drill pipe; 40 sacks at 360'; solid bridge at 40'  
with 1/2 sack hulls, Howco plug, 10 sacks to  
surface. 5 sacks in rat hole. Used 50/50  
Pozmix by Howco.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE  
F. A. Wuellner (employee of owner) or owner or operator

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, Kansas 67579  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December, 19 79.

My commission expires \_\_\_\_\_



[Signature]  
Charles M. Hall, Notary Public.

STATE RECEIVED  
DEC 26 1979  
CONSERVATION DIVISION  
Wichita, Kansas  
12-26-79

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- SCHAEFER #1  
Located: SW NE, Section 17-27S-14W, Pratt County, Kansas

OWNER: Beren Corporation  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 29, 1979  
COMPLETED: December 13, 1979

TOTAL DEPTH: 4560'

LOG

0 - 200 Sand and Clay  
200 - 250 Sand and Gravel  
250 - 432 Shale  
432 - 1500 Shale and Red Bed  
1500 - 3312 Lime and Shale  
3312 - 3590 Lime  
3590 - 3845 Lime and Shale  
3845 - 4085 Lime  
4085 - 4090 Lime and Shale  
4090 - 4140 Lime  
4140 - 4150 Lime and Shale  
4150 - 4195 Lime  
4195 - 4315 Lime and Shale  
4315 - 4480 Lime  
4480 - 4515 Lime and Shale  
4515 - 4560 Lime

CASING RECORD

Ran 9 joints 8 5/8" casing, 364' set at  
378' K.B. Cemented with 290 sacks 60/40  
Pozmix with 3% cc. Plug down at 9:00 PM,  
11-29-79, by Howco.

Plugged.

Deviation Surveys:

RECEIVED  
STATE CONSERVATION COMMISSION

DEC 26 1979

CONSERVATION DIVISION  
Wichita, Kansas  
1 1/2° at 4423'