


NORTH



Locate well correctly on above
Section Plat

Cowley County. Sec. 31 Twp. 32 Rge. 4 (E) E (W)
Location as "NE/CNW/SW" or footage from lines. SE NE NE
Lease Owner K. T. Wiedemann
Lease Name Elam Stayton Well No. 5
Office Address Box 285, El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed Feb. 25, 19 53
Application for plugging filed May 28, 19 52
Application for plugging approved May 28, 19 52
Plugging commenced Feb. 25, 19 53
Plugging completed Feb. 25, 19 53
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. S. Lemaster
Producing formation Depth to top Bottom Total Depth of Well 3161 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	122	
				5 1/2	3122	2500

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cement from 3161 to 3150
Plastic hydromite to 3100
Heavy mud 200
Rock bridge covered
with 15 sx. cement 145
Mud 25
Cement 0

(If additional description is necessary, use BACK of this sheet)



Name of Plugging Contractor Company tools -
Address El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
I. J. Sledge (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) X L. J. Sledge

SUBSCRIBED AND SWORN TO before me this 2 day of March, 19 53

My commission expires 12-5-55 Notary Public.



Elam Stayton #5

Total Rotary 3122
Comm. Rotary 7-6-51
Comp. Rot. 7-23-51

SE NE NE
Sec. 31-32-4E
Cowley County
Kansas


Cable Tools
Comm. 7-28-51
Comp. 2-25-53

Cement
8 5/8" Surface w/95 sx.
5 1/2" Oil string w/45 sx.
United Cementing Co.

Figures Indicate Bottom of Formations
Rotary Bushing 4.8' to ground level

cellar	5
clay	20
lime & shale	205
lime	457
Red Rock	477
lime 7 shale brks	650
shale & shells	920
sand	945
sandy shale	1010
lime	1050
shale & shells	1370
lime & shale	1665
lime	1742
shale	1895
lime & shale brks	1950
shale	2025
shale & lime	2030
shale	2115
lime & shale brks	2160
lime	2175
lime & shale	2340
shale	2540
sandy shale	2565
shale & shells	2595
shale	2658
lime	2769
shale	2785
lime & shale	2885
lime	2955
1665 lime & shale	3010
shale	3119
sand	3122
Cable tools	R.T.D.
sand	3160
lime	3161 TD

Pulled 2500ft. 5 1/2" oil string
Plugged & abandoned



RECEIVED
STATE CORPORATION COMMISSION
MAR - 4 1953
CONSERVATION DIVISION
Wichita, Kansas