

TATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-035-23201

LEASE NAME Johnson "A"

WELL NUMBER 1

990 Ft. from S Section Line

1815 Ft. from E Section Line

SEC. 31 TWP. 32S RGE. 4 (E)

COUNTY Cowley

Date Well Completed Dec. 5, 1982

Plugging Commenced Aug. 19, 1997

Plugging Completed Aug. 21, 1997

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Keith D. Leake

ADDRESS R.R. 3 Box 160 Winfield, Kansas 67156

PHONE#(316-221-1247) OPERATORS LICENSE NO. 5998

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Jerry Clark (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Bartlesville Depth to Top _____ Bottom _____ T.D. 3269'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| Surface | | 0' | | 8 5/8 | 216 | 0 |
| Bartville | water | 0' | | 4 1/2 | 3269 | 1812' |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Plugged bottom with rock, spotted 5 sks of cement on rock with dump bailer, shot at 1812', pulled 4 1/2" casing, ran tubing to 1812', filled to surface with slurry mix cement, Daniels Ready Mix #51602.

Name of Plugging Contractor Cooper Service Company License No. 31865

Address P.O. Box 381 Winfield, Kansas 67156

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Keith D. Leake

STATE OF Kansas COUNTY OF Cowley, ss.

Albert L. Cooper dba, Cooper Service Company (Employee of Operator), or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Albert L. Cooper

(Address) P.O. Box 381 Winfield, Ks. 67156

SUBSCRIBED AND SWORN TO before me this 5th day of Sept., 19 97

Gretchen Marler
Notary Public

My Commission Expires: 6-10-2001

