

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 7 TWP. 27S RGE. 14 E/W
Location as in quarters or footage from lines:
150' SE of SE, SW, SW

Lease Owner Texas Energies, Inc.
Lease Name Jones Well No. 1-7
Office Address P. O. Box 947 Pratt, Kansas 67124
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 7-19-81
Application for plugging filed 7-20-81
Plugging commenced 7-19-81
Plugging completed 7-19-81
Reason for abandonment of well or producing formation
Dry - Abandoned

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom _____ T.D. 4710 ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged as follows:
1st plug at 620' Cemented w/50 sks
2nd plug as 290' Cemented w/40 sks
Mud to 40' Solid Bridge w/10 sks
10 sks Rat hole
2 sks water well
Cement - 112 sks Common 2% Gel 3% CC
Plug set & job complete at 11:30 P.M. 7-19-81

RECEIVED
STATE CORPORATION COMMISSION
7-22-81
JUL 22 1981
CONSERVATION DIVISION
Wichita, Kansas

Witnesses: Michael Gray, Charles Ross, Marvin Brothers, Richard Piehler
(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Landmark Energy Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
R. L. Smith (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.


(Signature) [Signature]
R. L. Smith, President

(Address)
P. O. Box 18595 Wichita, Ks. 67218

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 81

Judy Jo Peterson
Judy Jo Peterson Notary Public.

My Commission expires: 6-18-83





P.O. Box 18595 / Wichita, KS 67218

Wichita (316) 262-3071
(316) 685-1401

Great Bend (316) 793-5285

Mobile (316) 672-5663
Unit 2904

Rig #1 (316) 672-5663
Unit 2905

DRILLERS' WELL LOG

Jones #1-7
150' SE of SE, SW, SW, Section 7, TWP 27S, R14W
Pratt County, Kansas

Commenced: 7-5-81

Completed: 7-19-81

OPERATOR: Texas Energies, Inc.


<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	190	Sand	Spudded at 12:05 A.M. 7-6-81
190	330	Redbed	Ran 7 joints 8 5/8" csg set @ 294'
330	2450	Sand & Shale	Cemented w/125 sks Howcolite 3% CC
2450	4090	Lime & Shale	125 sks Common 2% Gel, 3% CC
4090	4150	Kansas City Lime	Job complete at 9:00 A.M. 7-6-81
4150	4440	Lime & Shale	
4440	4500	Mississippi Lime	Total depth of well 4710 ft.
4500	4525	Viola Sand	D.A. plugged with 112 sks Common
4525	4690	Lime & Shale	2% Gel, 3% CC
4690	4710	Arbuckle	1st plug at 620' w/50 sks
			2nd plug at 290' w/40 sks
			Solid brige plug at 40' w/10 sks
			10 sks rat hole, 2 sks water well
			Job complete 11:30 P.M. 7-19-81

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATION COMMISSION

I, the undersigned, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

JUL 22 1981
CONSERVATION DIVISION
Wichita, Kansas
LANDMARK ENERGY CORPORATION

BY: 
R. L. Smith, President

JUDY JO PETERSON
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KS.
MY APPL. EXPIRES 6-18-83
KANSAS

My Commission Expires:
6-18-83


Judy Jo Peterson