

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Texas Energies, Inc.

Complete Address 300 Bank of the Southwest Bldg., Amarillo, Texas. 79109

Lease Name McBride Well No. 1

Location C NW NE Sec. 34 Twp. 27s Rge. 14 (E) (W) X

County Pratt Total Depth 4634

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Sargent's Casing Pulling.

Address 620 S. Lincoln, Liberal, Ks. 67901 License No. 511

Operation Completed: Hour 9:30 Am. Day 19 Month 5 Year 1979

The above well was plugged as follows:

437' 8 5/8" casing w/350 sax cement. 5 1/2" casing set at 4200' w/125  
sax cement. Pref., at 4066'. Steel bridge plug @ 4020' - 1 3/4" Hydrojet  
@ 3938' - Pump 50 sax common cement in 5 1/2" casing from 4020' back to  
3125' - Spot 20 sax gel at 1700' - Spot 40 sax cement at 400' - Spot 12 sax  
cement at 40' to top of casing. Recovered 2605' 5 1/2" casing. Cement  
pumped by Sargent's Casing Pulling.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 23 1979 5-23-79

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 5-23-79  
INV. NO. 9688-W