

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Co. Inc.

Complete Address 200 W. Douglas Wichita, Ks

Lease Name Newby Well No. 1

Location NW/SE/NW Sec. 14 Twp. 27 Rge. 15 (E) (W) W

County Pratt Total Depth 4558

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 2:00 PM Day 2 Month 11 Year 1970

The above well was plugged as follows:

300 ft of 8 5/8 surface pipe circulated. 4535 ft of 4 1/2 long string
cemented with 200 sacks. Top perf. 4442 ft. Sand back to 4400 ft,
4 sacks cement with bailer. Pulled 3294 ft of 4 1/2. Set 10 ft rock
bridge at 275 ft. Fill hole with 4 yds redimix to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russell Bibrstein
Well Plugging Supervisor

DATE 11/4/70
INV. NO. 2807-W