

15-167-04021-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW-NW-NW

SEC. 14 TWP. 14 RGE. 14W

Dry Hole \*\*\* Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 7 Lease Henry Boxberger

Operator The Texas Co. Address Rt. #1. Russell, Kansas.

Field \_\_\_\_\_ County Russell

Total Depth 3320' Feet.

Plugging Contractor Stickle Brillling Co.

Plugging Contractor's License No. \_\_\_\_\_

Address 920 - 10th. Nat'l. Bk. Bldg. Tulsa, Okla.

(Describe briefly the manner in which the well was plugged)

Surface pipe -10 3/4" @ 841' c.w.c. 625 sx. Run drill pipe to bottom  
open ended. Had Halliburton pump in 155 sx. cem. through drill pipe.  
Then pulled pipe out and mud to 300' from top, 1/2sx. hulls, H.O.W.C.O.  
plug and 25 sx. cem. pumped through pipe used to push plug to required  
depth. Pulled the 300' of pipe out, then mud to 40' from top, 1/2 sx.  
hulls, H.o.w.c.o. plug and pumped in 20 sx. cem. to base of cellar.

*Milton G. Gahardt*  
District Conservation Agent

Date 3-19-56

RECEIVED  
MAR 21 1956  
CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 14 T 14 R 14W  
BOOK PAGE 47 LINE 5

CP3