

ANS
WCC
LEASE NAME Oshlo

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER A-3
_____ Ft. from S Section Line
_____ Ft. from E Section Line

LEASE OPERATOR Pickrell Drilling Co., Inc.

SEC. 5 TWP. 30S RGE. 24W (E) or (W)

ADDRESS 110 N. Market, Suite 205 Wichita, KS 67202

COUNTY Clark

PHONE#(316) 262-8427 OPERATORS LICENSE NO. 5123

Date Well Completed _____

Character of Well Oil

Plugging Commenced 11-8-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-22-93

The plugging proposal was approved on _____ (date)
by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5442'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	514	none
				4 1/2	5420	2700

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Sanded bottom to 5200' & 4 sks cement. Shot @ 2700', came loose. Pulled pipe. Ran tubing to 1240', pumped 50 sks cement. Pulled to 540', pumped 50 sks cement. Pulled to 90', pumped 25 sk cement. Pulled rest of pipe, topped off with 10 sks cement. 60/40 pos 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Co., Inc.

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) *R. Darrell Kelso*

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 8th day of December

Diane Herzberg
Notary Public

My Commission Expires: _____



RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1993
CONSERVATION DIVISION
Wichita, Kansas Form CP-4
Revised 05-88