


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Pratt County, Sec. 13 Twp. 27 Rge. 15 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner United States Hydrocarbon Company
Lease Name Jones #2 Well No. _____
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/25/69 _____ 19____
Plugging completed 7/3/69 _____ 19____
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4740 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	328'	none
				4 1/2"	4739'	2458'
RECEIVED STATE CORPORATION COMMISSION JUL 10 1969 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole to 4225', set 5 sacks of cement.
Shot pipe at 3190', 3100', 3020', 2894', 2662', 2564', 2468';
worked pipe loose and pulled 75 joints. Pumped 10 sacks of
mud and 75 sacks of cement. Capped with 2 sacks of cement.

PLUGGING COMPLETE.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

7th day of July, 1969



Margaret Melcher Notary Public.

D R I L L E R S L O G

#2 Jones

CASING RECORD:
Ran 328' of new 8-5/8"
surface casing.

COMPANY: United States Hydrocarbon Co.

DESCRIPTION: C/NE ^{SW}
Section 13-27S-15W
Pratt County, Kansas

TOTAL DEPTH:
4740'

COMMENCED: April 7, 1967

ELEVATION: 2044' RB

COMPLETED: April 22, 1967

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay	0	55	Ran 328' of new 8-5/8" surface casing; set and cemented at 328' with 230 sacks of common cement and 2% gel. Plug down at 12:45 P. M. April 8, 1967.
Sand	55	105	
Shale, Sand & Shells	105	920	
Shale	920	979	
Anhydrite	979	993	
Shale	993	1010	
Shale & Shells	1010	1790	
Lime & Shale	1790	4020	
Lime	4020	4035	
Lime & Shale	4035	4096	
Lime	4096	4136	
Lime & Shale	4136	4155	
Lime	4155	4185	
Lime & Shale	4185	4255	
Lime	4255	4275	
Lime & Shale	4275	4362	
Lime & Chert	4362	4460	
Lime & Shale	4460	4468	
Lime	4468	4500	
Cherty Lime	4500	4503	
Lime, Shale w/Chert Streaks	4503	4532	
Lime & Chert	4532	4575	
Cherty Lime	4575	4603	
Lime, Shale w/Chert Streaks	4603	4651	
Lime & Sand	4651	4685	
Sandy Lime & Shale	4685	4700	
Lime w/Chert Streaks	4700	4740	
Total Depth	4740'		Ran 146 joints of new 4 1/2"; set and cemented at 4739' with 300 sacks of posmix, salt saturated and 15 barrels of brine ahead of cement. Plug down at 10:45 P. M. April 22, 1967.

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1969
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Jim B. McWilliams
Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 24th day of April, 1967.

My Commission Expires:

Elaine H. Taylor
Elaine H. Taylor, Notary Public

December 14, 1969