


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Pratt County, Sec. 13 Twp. 27 Rge. 15 (E) (W)
 Location as "NE/CNW/SW" or footage from lines. NW NW NE
 Lease Owner R. C. Combee
 Lease Name Jones C#1 Well No.
 Office Address Liberal, Kansas 67901
 Character of Well (completed as Oil, Gas or Dry Hole)
 Date well completed 19
 Application for plugging filed 19
 Application for plugging approved 19
 Plugging commenced 3/29/74 19
 Plugging completed 4/3/74 19
 Reason for abandonment of well or producing formation depleted.
 If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
 Producing formation Depth to top Bottom Total Depth of Well 4535 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	328	none
				4 1/2"	4271	2524'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4335', ran sand to 4250' and ran 3 sacks cement. Shot pipe at 3471', 3261', 3113', 2908', 2718', 2512', pulled 72 joints of 4 1/2" casing. Pumped 2 sacks hulls, 10 sacks gel and 100 sacks cement.

PLUGGING COMPLETE.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 9 - 1974
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor EBBE KNIGHT CASING PULLING CO., INC.
 Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
 NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
 CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of April, 1974

MARGARET MELCHER
 NOTARY PUBLIC
 Rice County, Kansas
 My Commission Expires Feb. 15, 1975

Margaret Melcher
 Notary Public.

DRILLERS LOG

#1 Jones "C"

CASING RECORD:
328.76' of new 8-5/8"
surface casing.

COMPANY: Strata Drilling, Inc.
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: NW NW NE
Section 13-27S-15W
PRATT, CO.

TOTAL DEPTH:
4535'

COMMENCED: January 2, 1968
COMPLETED: January 15, 1968

ELEVATION: 2043' DP

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Shale	0	380	Ran 328.76' of new 8-5/8" surface casing; set and cemented at 328.76' with 240 sacks of regular cement, 2% gel, 4% calcium chloride. Plug down at 6:30 P. M. January 3, 1968.
Shale & Shells	380	1987	
Lime & Shale	1987	2670	
Shale	2670	3234	
Shale & Lime	3234	3945	
Lime	3945	4485	
Lime & Chert	4485	4495	
Lime	4495	4535	

Total Depth 4535'

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1974
CONSERVATION DIVISION
Wichita, Kansas

DRILLER

Ran 4271.59' of new and used 4 1/2"; set and cemented at 4271.59' with 200 sacks of 60-40 posmix, 10 sacks of salt flush ran ahead of cement. Plug down at 2:30 P. M. January 15, 1968.


STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

J. B. McWilliams
J. B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 16th day of January, 1968.



Elaine H. Taylor
Elaine H. Taylor, Notary Public