



KANSAS

Form CP-3
Rev. 6-9-67STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION

AUG 25 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202Intent to Drill,
filed August 11, 1967.CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name California-Time Petroleum, Inc.
 Complete Address Suite 515, Union National Bank Bldg., Wilshire Blvd., Beverly Hills, Calif.
 Lease Name Jones-Maas Well No. # 2
 Location C 1/2 N 1/2 SE
440' FNL 1320' NWL SE Sec. 13 Twp. 27 Rge. 15 (E) (W) W
 County Pratt Total Depth 4630'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated
 Plugging Contractor Strata Drilling, Inc.
 Address 2421 Tenth St., Great Bend, Ks. 67530 License No.
 Operation Completed: Hour 6:00 P.M. Day 24th Month August Year 1967

The above well was plugged as follows:

360' of 10 3/4" surface pipe, cement circulated with 300 sacks. Fluid
level in the hole was at 60', 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 300', and cemented with 30 sacks, through the
drill pipe, with cement from 300' to 240'. Hole was filled with drilling
mud to 40', 2nd cementing plug, bridged with 1 sack of dry cement and
1/2 sack of hulls on fluid at 40', and cemented with 14 sacks, with cement
from 30' to the base of the cellar. Rat and mouse holes bridged and cem-
ented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 8-28-67
INV. NO. 6206-W