

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 144-13LOCATION C27/2-22W-22NSEC. 12 TWP. 28 RGE. 11WDry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease HumpOperator Ohio Petco. Co Address Box 671 - Russell-Kans.Field _____ County PrattTotal Depth 4232 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4" - 375 ft. Circulated with cement
5 1/2" casing at 4243 ft. Plugged back to 4230 ft with
sand & Chat. Dumped 5 sacks of cement at 4230 ft
Shot off & pulled the 5 1/2" casing. Filled with mud
& 375 ft. Set Rock bridge & 15 sacks of cement at 375 ft
Mud to 30 ft. Plug & 10 sacks of cement
at the surface.

Frank Carroll - Plugger

RECEIVED

Conservation Div.

04-10-50

APR 10 1950

STATE CORPORATION
COMMISSION

District Conservation Agent

Date 4-6-50