

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 66-8

LOCATION NW-NE-27E

SEC. 11 TWP. 28 RGE. 11-W

Dry Hole Abandoned Oil Well Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease Buehlin

Operator Mr. S. K. Meyers Address 1311 Madison St. Great Bend - Kans.

Field County Peatt

Total Depth 4246 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 368 ft - Circulated with cement.
5/8" casing set at 4246 ft - Plugged back from bottom
to 4200 ft with sand & cement - Run 5 sacks of
cement at 4200 ft - Shot off & pulled the 5/8" casing - Filled
with mud to 250 ft - Set Pack Bridges & 20 sacks cement at 250 ft
Mud to 20 ft - Plug & 10 sacks of cement at the surface
Patterson & Son - Plugging - Contractors

RECORDED

12-13-48
DEC 1

C. M. Stough -
District Conservation Agent

Date 12-11-48

PLUGGING
FILE SEC 11 T 28 R 11 W
BOOK PAGE 66 LINE 8