

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 132-30LOCATION E/2-SE-7WSEC. 3 TWP. 18 RGE. 11WDry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Francis H. SeltonOperator Gulf Oil Corp Address Box 661, Tulsa, Okla.Field _____ County PrattTotal Depth 3535 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 7/8 - 395 ft. Circulated with cement
5 1/2 casing set at 3570 ft - Plugged back from bottom to 3500 ft
with chat - Dumped 5 sacks of cement at 3500 ft - Filled with
mud to 250 ft - Set Arch Bridge & 15 sacks of cement
at 250 ft - Mud to 30 ft - Bridge & 10 sacks of cement at
the surface -

General Oil Tool Co. Plugging Contractors

01-19-50
JAN 19 1950

E. H. Stough
District Conservation Agent

Date 1-19-50