

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 121-26LOCATION CE 2. SE-SWSEC. 3 TWP. 28 RGE. 11-WDry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease SillonOperator Sunray Oil Corp Address Box # 195 - G. Bend - KansasField _____ County PrattTotal Depth 3622 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/8" 425 ft. Circulated with cement
5 1/2" casing set at 3560 ft. Plugged back from
bottom to 3560 ft with chat. Pumped 5 sacks of
cement at 3560 ft. Shot off & pulled the 5 1/2" casing -
Filled with mud to 425 ft. Pumped in Plug &
150 sacks of cement. Filling hole from 425 ft. to
the surface with cement. By Halliburton
Jim Forbes.

Plugging Contractor

C. A. Stough -
District Conservation AgentDate 11-15-49

NOV 15 1949 11-15-49

STATE CORPORATION
COMMISSION
KANSAS