

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 7-37

LOCATION N.E. N.E.

SEC. 7 TWP. 28 RGE. 11 N

Dry Hole Rotary Abandoned Oil Well Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease Gilchrest

Operator Kinwood Oil Co. Address Effingham Illinois Box 450

Field County Pratt

Total Depth 4520 Feet.

(Describe briefly the manner in which the well was plugged)

Hole was plugged 4520 to 3740 with mud. Crushed rock bridge at 3740. Cement 3740 to 3720. 5 sacks. Mud 3720 to bridge at 350 ft wood & rock. Cement 350 to 320. 15 sacks. Mud 320 to 15 ft. Cement to base of pillar. 10 sacks. 351 ft of 10 1/2" pipe cemented & lapped in hole.

*pd.
5/7/45
Ho.*

PLUGGING
WELL NO. 7-28-114
BOOK 7-37

H. W. [Signature]
District Conservation Agent
Date April 16, 1945

