

6-21

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-20,594-00-00

C NE NW, SECTION 11 TOWNSHIP 31 RANGE 7W

OPERATOR LICENSE # 5822 4620 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR Val Energy
NAME & Box 322
ADDRESS Haysville, KS 67060

LEASE NAME: Bolles #4

COUNTY: Harper 141.666

WELL TOTAL DEPTH: 4359 PB 4343'

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 260'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Co Tools

ADDRESS: _____ LICENSE: 5822

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Todd Allan

COMPANY NAME: Val Energy PHONE: _____

WERE: 4-1/2 4358', Perfs 4330-36', Tight spot 3500' - Sand back to 4250'- Set CIBP @ 3450'- 35sx @ 1250'- 35sx @ 800'- circ 310'

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 13:00 DAY: 21 MONTH: 6 YEAR: 1993

ACTUAL PLUGGING REPORT:

The perfs were covered with sand to 4250' -Due to tight spot at 3500' the bailer would not go through to spot cmt on top of the sand. A CIBP was set at 3443' and capped with 4sx of cmt. The 4-1/2" was shot off at 2970' and pulled to 1239' where 35sx cmt was spotted. The 4-1/2" was then pulled to 783' where 35sx cmt was spotted. The 4-1/2" was then pulled to 327' where cmt was circ to surface.

REMARKS: Allied Cmt 60/40 4% gel

I DID OBSERVE THIS PLUGGING.

INVOICED

Steve Van Gieson
Steve Van Gieson (AGENT)

DATE 6-30-93

WV. NO. 38031

DW