

1020778

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,259-00-00

7-14

G-W/2 SW , SEC. 21 , T 32 S, R 28 W, XX
1320 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30208

Lease Name Crooked L Ranch Well # 1-21

Operator: Tri-J Tubulars, Inc.

County Meade

Name & Address 225 N. Market, Ste. 300

Well Total Depth 5580 181.35 feet

Wichita, KS 67202

Conductor Pipe: Size 13 3/8 feet 920

Surface Casing: Size 8 5/8 feet 1305

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor D.S. & W. Well Servicing, Inc. License Number 6901

Address P.O. Box 213, Claflin, KS 67525

Company to plug at: Hour: 9 a.m. Day: 14 Month: 7 Year: 19 94

Plugging proposal received from Kevin Strube

(company name) D.S. & W. Well Servicing, Inc. (phone) 316-587-3361

logs: 5 1/2" at 5540' w/225 sx cement, PBTD 5498', Perfs at 5427-30'

1st plug set CIBP at 5375',.

2nd plug at 1330' with 50 sx cement,

3rd plug at 600' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:45 p.m. Day: 14 Month: 7 Year: 1994

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5375',

2nd plug pumped 50 sx cement at 1340', pulled to 890' and pumped 5 sx gel,

3rd plug pumped 40 sx cement at 650',

4th plug pulled 5 1/2" and filled 8 5/8" to surface,

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.)

DATE 7-21-94

REV. NO. 40848

Signed Glenn R. Barber
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas