

To: 1 031435. 1-8
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 119-20,975-00-00
SW SW, SEC. 10, T 32 S, R 28 WEX
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7382
Operator: KWB Oil Property Management, Inc.
Name & Address: 20 E. 5th St., Ste. 1100
Tulsa, OK 74103-4439

Lease Name Ediger Well # 1
County Meade 182.00
Well Total Depth 5600 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1660

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A
Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684
Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: _____ Day: 8 Month: 1 Year: 19 97

Plugging proposal received from Bill Craig
(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 1670' with 50 sx cement, 2nd plug at 600' with 40 sx cement,
3rd plug at 40-0' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11 p.m. Day: 8 Month: 1 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1670' with 50 sx cement,
2nd plug at 600' with 40 sx cement,
3rd plug at 40-0' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

1-13-97

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

DATE JAN 15 1997

Signed Steve Durrant (TECHNICIAN)

INV. NO. 47378
1-8

EFFECTIVE DATE: 11-24-96

State of Kansas

NOTICE OF INTENTION TO DRILL 119-20,975-00-00

DISTRICT # 1
SSA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date .. November 15 .. 1996 ..
month day year

SW SW Sec 10 Twp 32 S Rg 28 East West

OPERATOR: License # 07382
Name: KWB Oil Property Management, Inc.
Address: 20 E. 5th St., Suite 1100
City/State/Zip: Tulsa OK 74103-4439
Contact Person: Charles A. Ellis
Phone: (918) 583-8300 ext 207

660 feet from South ~~XXXX~~ line of Section
660 feet from ~~XXXX~~ West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 30684
Name: Abercrombie RTD, Inc.

County: Meade
Lease Name: Ediger Well #: 1
Field Name: Wildcat

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): Morrow Sand

Nearest lease or well boundary: 360'

Ground Surface Elevation: 2492' feet MSL

Water well within one-quarter mile: yes X no

* Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 310'

Depth to bottom of usable water: 420'

Surface Pipe by Alternate: X 1 2

Length of Surface Pipe Planned to be set: 1450' *

Length of Conductor pipe required: to be determined

Projected Total Depth: 5600'

Formation at Total Depth: Morrow

Water Source for Drilling Operations:

well farm pond X other

DWR Permit #: _____

Will Cores be Taken? yes X no

If yes, proposed zone: _____

* (thru Glorietta) 440' Alt. I Req.

Well Drilled For: Well Class: Type Equipment:
Oil Enh Rec Infield X Mud Rotary
X Gas Storage Pool Ext. Air Rotary
OAWO Disposal X Wildcat Cable
Seismic: # of Holes Other
Other

If OAWO: old well information as follows:

Operator: _____

Well Name: _____

Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes X no

If yes, true vertical depth: _____

Bottom Hole Location: _____

Exp. 5/19/97

AFFIDAVIT

* PUBLIC WATER SUPPLY IN SEC 10-32-28

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Bill Caray
SPUD DATE 12-27-96 INIT. SD
LENGTH SURFACE PLANNED 1660 ±
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 5 1/2 @ 1660 CONDUCTOR
ANHYDRITE T- B- ELEVATION
TD 5600 FORMATION MISS.
RAN PIPE @ DV TOOL ALT II DONE
Arbuckle Plug @ Ft. W/ SX Y N SX
Aug./Council @ Ft. W/ SX
Anhydrite Base @ 1670 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
2 1/2, 1/2 Plug @ 600 Ft. W/ 40 SX
Bottom Surface @ Ft. W/ SX
3 40' Plug @ 40-0 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 12 SX
WATER WELL SX (Irr. Well Pond Hauling X)
TECHNICIAN SD DATE 1/07/97 60/40 Pkg 60/60
TYPE OF CEMENT
STARTING TIME (AM/PM) DATE
COMPLETION TIME 11:00 (AM/PM) DATE 1-8-97
CEMENT COMPANY H.A. Hubert Co