

To: 1 100200 2-18  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-119-20,579-00-00  
C NW NE, SEC. 36, T 32 S, R 28 WXX  
4620 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 3871

Lease Name Lowen D Well # 1

Operator: Hugoton Energy Corporation  
Name & Address 301 N. Main, Ste. 1900  
Wichita, KS 67202

County Meade 188.50

Well Total Depth 5800 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1507

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524-0209

Company to plug at: Hour: 2 p.m. Day: 18 Month: 2 Year: 19 98

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

work: 4 1/2" at 5721' w/200 sx cement, PBD 5695', Perfs at 5655-58', TOC 4100'

1st plug sand back to 5600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 50 sx cement with 15 sx gel at 1530',

3rd plug pump 40 sx cement at 600',

4th plug pump 20 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:40 p.m. Day: 18 Month: 2 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand through bailer,

2nd plug spotted 50 sx cement at 1530', displaced with gel,

3rd plug spotted 40 sx cement at 600', displaced with gel,

4th plug spotted 20 sx cement at 40-0'.

RECEIVED  
STATE CORPORATION COMMISSION  
2-25-98  
FEB 25 1998

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3500' of 4 1/2" casing  
(if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE FEB 26 1998

Signed Gary Winters (TECHNICIAN)

INV. NO. 50158