

7-27

2-

15-077-10262-00-00

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: \_\_\_\_\_ SPUD DATE 1/15/64  
C NE SE, SECTION 13 TOWNSHIP 31 RANGE 7W

OPERATOR LICENSE # 6581 1320 FEET FROM S SECTION LINE  
1320 FEET FROM E SECTION LINE

OPERATOR BISON ENERGY CORP  
NAME & 9320 EAST CENTRAL  
ADDRESS WICHITA KS 67206

LEASE NAME: PALMER 2A  
COUNTY: HARPER  
WELL TOTAL DEPTH: 4719' 153.36

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 242'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE  
ADDRESS: ATTICA, KS LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: JEFF CAPPS  
COMPANY NAME: SHAWNEE WELL SERVICE PHONE: \_\_\_\_\_

WERE: 4-1/2" @ 4453' - PERFS 4298'-4573' - 30 SX @ 1100' -  
30 SX @ 800' - CIRCULATE FROM 267'

PLUGGING PROPOSAL RECEIVED BY: STEVE VAN GIESON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART (  ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 1330 DAY: 27 MONTH: 7 YEAR: 1993

ACTUAL PLUGGING REPORT:  
PERFS SANDED BACK TO 4250' & CAPPED W/4 SX CMT -  
4-1/2" RECOVERED FROM 2050' - PULLED TO 1135' &  
30 SX CMT SPOTTED - 4-1/2" PULLED TO 811' & 30 SX CMT  
SPOTTED - 4-1/2" PULLED TO 267' & CMT CIRC  
REMAINING CASING PULLED & CMT WAS TOPPED OFF

REMARKS: ALLIED 60/40 4%

I DID OBSERVE THIS PLUGGING.

OCT 12 1993  
10-12-93  
CONSERVATION DIVISION  
WICHITA, KS

Steve Van Gieson (AGENT)

INVOICED

DATE 10-13-93

INV. NO. 38931