

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20340-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 32-24S-40W  
330 feet from N Section Line, 330 feet from W Section Line  
Lease Name: FEDERAL Well #: 1-32  
County: HAMILTON Total Vertical Depth: 2450 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>32334</u>	PROD	4.5	2450	0	WITH 550 SX CMT
Op Name: <u>CHESAPEAKE OPERATING, LLC</u>	SURF	8.625	541		WITH 400 SX CMT
Address: <u>6100 N WESTERN AVE PO BOX 18496</u> <u>OKLAHOMA CITY, OK 73118</u>					

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2014 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/18/2014 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 90 SX CMT WITH 200# HULLS DOWN 4 1/2" CASING TO 2386'. DISPLACE WITH 9# MUD TO 1200'. PRESSURE UP & TEST CASING TO 700#. HOLDING. RUN CBL FROM 1340' TO 0'. TOC @ 130'. RUN TBG TO 700' & CIRCULATE CMT TO SURFACE WITH 50 SX CMT. TOOH WITH TBG & TOP OFF 4 1/2" CASING WITH 10 SX CMT. ATTEMPT TO PUMP CMT DOWN THE ANNULUS TO 350#. COULD NOT.

Perfs:

Top	Bot	Thru	Comments
2378	2386		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED CLASS A COMMON CMT BY CONSOLIDATED.

Plugged through: TBG

District: 01

RECEIVED  
DEC 23 2014  
KCC DODGE CITY

Signed Ken Jehlik  
KCC WICHITA

JAN 12 2015

RECEIVED

ST