

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22385-00-00
Spot: E2NWNW Sec/Twnshp/Rge: 22-20S-27W
669 feet from N Section Line, 1018 feet from W Section Line
Lease Name: LOTTIE BURNETT Well #: 4-22-2027
County: LANE Total Vertical Depth: 4630 feet

Operator License No.: 33476
Op Name: DISCOVERY NATURAL RESOURCES L
Address: 410 17TH ST STE 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		3000		WITH 475 SX CMT
PROD	5.5	4629	0	WITH 700 SX CMT
SURF	8.625	376		WITH 240 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/31/2014 2:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GERALD WALKER Company: WALKER PUMPING Phone: (620) 793-2816

Proposed Plugging Method: PUMP 50 SX CMT & 200# HULLS ON BOTTOM. SPACER TO 2500' THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/31/2014 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 50 SX CMT & 300# HULLS THEN SPACER TO 2500' THEN PUMPED 235 SX CMT. MAXIMUM PRESSURE 2000#. SHUT IN CASING. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4524	4526		
4514	4516		
4505	4507		
4212	4213		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

1/14/15 CKM

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
JAN - 6 2015
KCC DODGE CITY

KCC WICHITA
JAN 08 2015
RECEIVED

SP