

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24513-00-03
Spot: SWSW **Sec/Twnshp/Rge:** 23-32S-6E
670 feet from S Section Line, 4670 feet from E Section Line
Lease Name: BAIR **Well #:** 1
County: COWLEY **Total Vertical Depth:** 3541 feet

Operator License No.: 34320
Op Name: LASSO ENERGY LLC
Address: PO BOX 465
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	5.5	3010		
PROD	5.5	3539	1866	225 sxs cmt
SURF	8.625	339		215 SX
T1	2.875	3002		

Well Type: OIL **UIC Docket No:** **Date/Time to Plug:** 09/17/2014 8:00 AM
Plug Co. License No.: 31529 **Plug Co. Name:** MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: KURTIS KELSO **Company:** MIKES TESTING & SALVAGE **Phone:** (620) 938-2534

Proposed Plugging Method: AS PER KCC RULES & R EGS

Plugging Proposal Received By: JEFF KLOCK **WitnessType:** PARTIAL
Date/Time Plugging Completed: 09/17/2014 8:00 AM **KCC Agent:** DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2600', DUMP BAILED 5 SXS CEMENT ON TOP. RIH ON WIRELINE SET CIBP @ 2250', DUMP BAILED 5 SXS CEMENT ON TOP. CUT CASING @ 1866', LAYED DOWN 5.5" CASING, (44 JOINTS, 1866'). RIH W/TBG @ 392', COPELAND ACID SERVICE ESTABLISHED CIRCUALTION, MIXED & PUMPED 160 SXS 60/40 POXMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 9/17/2014. COPELAND CEMENT TICKET # 42780.

Perfs:

Top	Bot	Thru	Comments
2866	2872	CSG	
2742	2748	CSG	
2704	2710	CSG	
2626	2632	CSG	
2446	2448	CSG	
2262	2263	CSG	

Remarks: CIBP SET @ 2250'

Plugged through: TBG

1/14/15 *ckm*

District: 02

Signed *Jeff Klock*
(TECHNICIAN)

KCC WICHITA
JAN 05 2015
RECEIVED