

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-23934-00-01
Spot: NWNESWSE Sec/Twnshp/Rge: 28-25S-15E
1320 feet from S Section Line, 1760 feet from E Section Line
Lease Name: HARTZLER Well #: 35
County: WOODSON Total Vertical Depth: 1223 feet

Operator License No.: 33900

Op Name: LEIS, STEVEN A.

Address: 1135 30TH RD
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1223		150 SX
SURF	7	40		10 SX

Well Type: EOR

UIC Docket No: E21983.9

Date/Time to Plug: 12/16/2014 12:00 AM

Plug Co. License No.: 33900

Plug Co. Name: LEIS, STEVEN A.

Proposal Rcvd. from: STEVE LEIS

Company:

Phone: (620) 330-6328

Proposed Plugging Method: 50ft at the bottom 50ft at the BK C and cement from 250ft to surface

Plugging Proposal Received By:

Witness Type: PARTIAL

Date/Time Plugging Completed: 12/16/2014 8:00 AM

KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2.875" casing to TD. Pumped and spotted 5 sacks of portland cement at TD. Pulled 1" pipe up to the Kansas City Formation. Pumped and spotted 3 sacks of portland cement at base of the Kansas City. Pulled 1" pipe up to 250'. Circulated cement from 250' to surface. Pulled the rest of the 1" pipe out of the hole and topped the well off with cement.

Perfs:

Top	Bot	Thru	Comments
1182	1184		
1174	1179		
1157	1171		

RECEIVED

JAN 07 2015

KCC Chanute Dist. #3

RD

Remarks:

Plugged through: TBG

District: 03

Signed

Received
KANSAS CORPORATION COMMISSION

JAN 09 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

cc:UIC