

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-21694-00-00  
Spot: SENESE Sec/Twnshp/Rge: 24-30S-8W  
2271 feet from S Section Line, 29 feet from E Section Line  
Lease Name: WSU Well #: 3  
County: KINGMAN Total Vertical Depth: 4500 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4494		805 SX
SURF	8.625	310		225 SX

Well Type: EOR UIC Docket No: E26857.3 Date/Time to Plug: 07/22/2014 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RANDY DICK Company: Phone: (620) 425-1000

Proposed Plugging Method: PLUGGER WILL PROVIDE ONCE ESTABLISHED

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/28/2014 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

DRIVE TO LOCATION, RAISED POLE, BLEW GAS OFF WELL, DUG CELLAR AND PIT, HAULED LOAD OF WATER, PUMPED 25 SXS CMT, 3% CC, 100# HULLS, SHOT TBG OFF AT 4044', PULLED 3 JTS TO 3945', PUMPED 10 SXS CMT, PULLED TUBING OUT, CUT HEAD OFF 4' BELOW GROUND, SET FLOOR, RAN TBG TO 1250', PUMPED 150 SXS CMT, 3% CC AT 1250', PULLED TBG OUT, TRIED TO RUN 1" DOWN 8 5/8", WOULDN'T GO, TORE DOWN FLOOR AND RIG, CLEANED UP LOCATION .

Perfs:


Top	Bot	Thru	Comments
4292	4334		
4242	4384		

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

KCC WICHITA

JAN 07 2015

RECEIVED

1/14/15 CKM

Form CP-2/3

cc: UIC ✓