

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-00055-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 17-30S-7W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: WELLS-TOWNER Well #: 1  
County: KINGMAN Total Vertical Depth: 4250 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 S MAIN STE 505  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4246		125 SX
SURF	8.625	160		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/18/2014 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID HOMMERTZHEIM Company: \_\_\_\_\_ Phone: (620) 793-2316

Proposed Plugging Method: See attached sketch and proposed procedure.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/19/2014 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

DROVE TO LOCATION, RAISED POLE, PUMPED 35 SXS, 100# HULLS TO 4100', SHOT TUBING OFF AT 792', PULLED TUBING OUT, PERFORATED AT 700', AND 250', DUG CELLAR AND PIT, RAN TUBING TO 792', PUMPED 50 SXS CEMENT, PULLED OUT, WAITED 2 HOURS, RAN IN TO TAG PLUG, NO CEMENT THERE, RAN TUBING TO 792', PUMPED 50 SXS CEMENT, PULLED TUBING OUT, WAITED 2 HOURS, TAGGED CEMENT AT 260', RAN TUBING TO 260', CIRCUALTED WITH 110 SXS CEMENT PULLED TUBING OUT, CUT WELL OFF 4' BELOW GROUND, TOPPED OFF WELL WITH 30 SXS CEMENT, FILLED CELLAR AND PIT IN.

Perfs:


Top	Bot	Thru	Comments
4147	4153		

Remarks:

Plugged through: TBG

District: 02

Signed

 1/14/15 CDM  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

JAN 02 2015

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3