

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-165-21740-00-00  
Spot: NWSENESE Sec/Twnshp/Rge: 30-16S-19W  
1830 feet from S Section Line, 500 feet from E Section Line  
Lease Name: SCHNEIDER Well #: 1  
County: RUSH Total Vertical Depth: 3920 feet

Operator License No.: 34134  
Op Name: TREK RESOURCES, INC.  
Address: 4925 GREENVILLE AVE., STE 915  
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3800		WITH 2 SX CMT
PROD	5.5	3919	0	WITH 500 SX CMT
SURF	8.625	217		WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/23/2014 10:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: JEFF Company: PROFESSIONAL PULLING SERVIC Phone: (785) 628-7443

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 12/23/2014 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 3800' WITH 2 SX CMT. RUN TBG TO 1480' & CIRCULATE 165 SX CMT TO SURFACE. PULLED TBG. TOPPED OFF WITH 30 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
3844	3846		
3841	3842		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

1/14/15 CPM

District: 01

Signed Michael Maier  
(TECHNICIAN)  
KCC WICHITA

RECEIVED  
DEC 23 2014  
KCC DODGE CITY

JAN 08 2015  
RECEIVED

SP