



15-025-20592-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

15 May 1982

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Herbert French of Picknell Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Picknell Drilling Co.

Complete Address: Sitwin Bldg. Suite 205, Wichita, Kansas 67202

Lease Name: Sioux Well No. C-1

Location: C-NE-SW Sec. 5 Twp. 30 Rge. 24 (E) (W)

County: Clark Total Depth: 5450'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. French was instructed to plug the well as follows:

They ran 467' of 8 5/8" surface casing & cement circulated it with 275 sks of cement. The anhydrite was topped at 1400'. 1st plug 1200' with 60 sks of cement. 2nd plug at 480' with 40 sks of cement. 3rd plug 40' to 0' on solid bridge with 10 sks of cement. Then circulated 10 sks of cement in rat hole. They pumped the cement through drill pipe with hole full of

Very truly yours,

(over)

Paul A. Luthis
Conservation Division Agent

MAY 18 1982
CONSERVATION DIVISION
Wichita, Kansas

heavy mud. The plugging was accomplished by
allied cementing

Paul A. Luthi