

R

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed August 11, 1967.

Dear Sir:

Mr. Gerd Steincamp of Strata Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: California-Time Petroleum, Inc.

Complete Address: Suite 515, Union National Bank Bldg., Beverly Hills, California
Wilshire Blvd.

Lease Name: Jones-Maas Well No. # 2

Location: 440'FNL 1320'NWL SE Sec.13 Twp. 27 Rge. 15(E)(W) W

County Pratt Total Depth 4630' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

360' of 10 3/4" surface pipe, cement circulated with 300 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 30 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 15 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent