



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 22 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Clyde Merckle of D. R. Lauck Oil Co., Inc. has this date requested permission to plug the following described well:

Mr. Merckle guarantees payment of the plugging fee.

Operator's full Name: D. R. Lauck Oil Co. & J. A. Aylward

Complete Address: 301 South Broadway, Wichita, Kansas

Lease Name: Bortz Well No. # 1

Location: NE SW SW Sec. 23 Twp. 28 Rge. 11 (E) (W) W

County Pratt Total Depth 4355 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Merckle was instructed to plug the well as follows:

243' of 8 5/8" surface pipe, cemented with 200 sacks. Fill hole with drilling mud to 240', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent