

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1966
7-29-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. H. G. Pankratz of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Pankratz guarantees payment of the plugging fee.

Operator's full Name: Jayhawk Oil Company

Complete Address: 412 One-Twenty Bldg., Wichita, Kansas

Lease Name: Rymph Well No. # 1

Location: C SW SW Sec. 11 Twp. 31 Rge. 7 (E)(W) W

County Harper Total Depth 4754' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pankratz was instructed to plug the well as follows:

327' of 8 5/8" surface pipe, cemented with 300 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent