

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
DEC 5 1966
12-5-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name E. E. Bickford
Complete Address: Box 3422, Wichita, Kansas
Lease Name Harding Well No. # 1
Location SE SE SW Sec. 7 Twp. 28 Rge. 11 (E) (W) W
County Pratt Total Depth 3900'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated: This hole was a wash down
Plugging Contractor: Glen & Smith Casing Pulling Company
Address: Box 156, Ellinwood, Kansas License No. 396
Operation Completed: Hour 4:00PM Day 29th Month Nov. Year 1966

The Above well was plugged as follows:

333' of 8 5/8" surface pipe, cemented with 250 sacks. 3800' of 2 1/2"
tubing for long string, cemented with 35 sacks. Top perferation 3640'.
10 sacks of cement was pumped on bottom, with the top of the cement
at 3400'. 3200' of 2 1/2" tubing was recovered from the hole. 20 sacks
of Gel-Mud and 80 sacks of cement was pumped into the surface pipe,
through an 8 5/8" swage, to a pressure of 200 lbs., bringing the top
of the cement to the base of the cellar. A wiping plug was run between
the mud and the cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/6/66

INV. NO. 4380-11