

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Authority to plug issued
April 9, 1976.

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1976
4-14-76
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name P. M. C. Inc.

Complete Address Box 1546, Liberal, Kansas 67901

Lease Name Collingwood Well No. 2

Location Sw. Sw. N.E. Sec. 8 Twp. 32 Rge. (E) (W) 27

County Meade Total Depth 3923

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Midwest Casing Pulling

Box F, Address Sublette, Kansas License No. 466

Operation Completed: Hour 4:00 PM Day 12 Month April Year 1976

The above well was plugged as follows:

There was 2640' of 8 1/8" surface casing,
350' of 16" surface casing. 4 1/2" was set
to 3923. Perforations were from 2958-2948
and 3636-3630. 1st plug at 3636 with
15 sacks cement and 2 sacks hulls. 4 1/2"
Pipe was cement to 2438. Shot & separated
at 2447. 2nd plug at 2250 with 35
sacks cement. 3rd plug at 40-0 with 15

I hereby certify that the above well was plugged as herein stated.

15401 CED 47' of salvage
Sacks Cement

Signed: Lawrence Thomas
Well Plugging Supervisor

DATE 4-14-76

INV. NO. 3065-W