

1 120052

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-01,001-00-01 *R*C NW SW, SEC. 8, T 28 S, R 11 W EX2095 feet from S section line4730 feet from E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 5278Lease Name Time Goyen Well # A-1Operator: Internorth, Inc. (for Northern Nat)County Pratt142.35

Name &amp;

Address P. O. Box 178Well Total Depth 4380 Simpson feetCunningham, KS 67035Conductor Pipe: Size        feetSurface Casing: Size 8 5/8 feet 260Abandoned Oil Well        Gas Well        Input Well        SWD Well        D&A XOther well as hereinafter indicated       Plugging Contractor Sterling DrillingLicense Number 5142Address P. O. Box 129, Sterling, KS 67579Company to plug at: Hour: 3:00 am Day: 5 Month: September Year: 1985Plugging proposal received from Ben Horsch(company name) Northern Natural Gas (phone) 316-298-5111

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1200' with 50 sx cement2nd plug at 310' with 50 sx cementsolid bridge3rd plug hulls - plug at 40' -- cement to surface with 10 sx cementPlugging Proposal Received by Don C. Ubel

(TECHNICIAN)

Plugging Operations attended by Agent?: All        Part        None XOperations Completed: Hour: 3:30 am Day: 5 Month: September Year: 1985ACTUAL PLUGGING REPORT 1st plug cemented 1350' drill pipe at 4377' with 140 sx cement,2nd plug at 1220' with 55 sx cement, 3rd plug at 310' with 100 sx cement - cementcirculated to surface, 4th plug to circulate rat hole with 15 sx cement.RECEIVED  
STATE CORPORATION COMMISSION*cemented drill pipe in hole*SEP 23 1985  
09-23-85CONSERVATION DIVISION  
Wichita, KansasRemarks: Used 60/40 Pozmix 6% gel

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 24 1985Signed Don C. Ubel  
(TECHNICIAN)INV. NO. 10233

9-5 OCT 09 1985

FORM CP-2/3  
Rev. 01-84