

1 010047

API NUMBER 15- 151-21,099 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW NE , SEC. 8 , T 28 S, R 11 W EX
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6140

Lease Name Minnie Goyan Well # 1

Operator: Longhorn Energy Resources

County Pratt

Name & Address P. O. Box 1314

Well Total Depth 4060 131.95 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 12:45 pm Day: 9 Month: December Year: 19 85

Plugging proposal received from Jim Rockhold

(company name) Rockhold (phone) 316-792-2506

were: 5 1/2" at 4050' PBTD 4030' Perfs at 3740-44'

1st plug sand back to 3690' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:05 pm Day: 9 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3690' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 250 psi

Remarks: Used 60/40 Pozmix 6% gel by Halliburton, Recovered 2500' 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby acknowledge and observe this plugging.

DATE DEC 20 1985

Signed Jack P. Luthi
(TECHNICIAN)

INV. NO. 11681

DEC 20 1985
12-20-85

12-9 JAN 15 1986 MAR 20 1986