

To: 1 090176
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-22
API NUMBER 15- 151-22,080-00-00 2000

SE SE NE, SEC. 23, T. 28 S, R. 11 W/E
2310 feet from N 2 section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5337
Operator: Nadel & Gussman
Name: _____
Address 3200 First National Tower
Tulsa, OK 74103

Lease Name Waylan Well # 1
County Pratt 151.12
Well Total Depth 4650 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929
Address 310 W. Central, Suite 117, Wichita, KS 67202

Company to plug at: Hour: 8 a.m. Day: 22 Month: 3 Year: 1992

Plugging proposal received from Ervin Neighbors
(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 700'
1st plug at 750' with 50 sx cement, 2nd plug at 340' with 50 sx cement;
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 9:30 a.m. Day: 22 Month: 3 Year: 1992

ACTUAL PLUGGING REPORT 1st plug at 750' with 50 sx cement,
2nd plug at 340' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

~~Inspector did not~~ observe this plugging.

INVOICED
DATE 4-14-92
INV. NO. 34952

RCW
04-14-92

Signed [Signature]
(TECHNICIAN)

EFFECTIVE DATE: 3-17-92

State of Kansas 15-151-22,080-00-00
NOTICE OF INTENTION TO DRILL

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

DISTRICT # 1
SSA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date March 15 1992
month day year

Spot SE SE NE Sec 23 Twp 28 S, Rg 11 East West

OPERATOR: License # 05337
Name: Nadel and Gussman
Address: 3200 First National Tower
City/State/Zip: Tulsa, OK 74103
Contact Person: Joe Anderson, Chief Engineer
Phone: 918/583-3333

2310 feet from SOUTH / North line of Section
330 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Pratt
Lease Name: WAYLAN Well #: 1
Field Name: Wildcat

CONTRACTOR: License #: 5929
Name: Duke Drilling Co. Lobo

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Mississippi/Arbuckle
Nearest Lease or unit boundary: 330'
Ground Surface Elevation: 1768 feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes ... Other

Water well within one-quarter mile: X yes no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 170'
Depth to bottom of usable water: 180'

If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 300
Length of Conductor pipe required: 0
Projected Total Depth: 4650
Formation at Total Depth: Arbuckle

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Water Source for Drilling Operations:
X well ... farm pond ... other
DWR Permit #:
Will Cores Be Taken?: yes X no
If yes, proposed zone:

200' Alt. I Req.

Exp. 9/12/92

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Sully
SPUD DATE 3-14-92 INIT. LWC
LENGTH SURFACE PLANNED 300
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 3 1/2" CONDUCTOR
ANHYDRITE T- B- 700 ELEVATION
TD 4650 FORMATION Arb
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ 50 SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 750 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 340 Ft. W/ 50 SX
40' Plug @ 10 Ft. W/ 10 SX
RAT HOLE CIRC/W 12 SX MOUSE HOLE W/ 12 SX
WATER WELL Fill SX (Irr. Well Pond)
TECHNICIAN SM DATE 3-14-92 Hauling
TYPE OF CEMENT 60/40 67
STARTING TIME 8:02 (AM/PM) DATE 3-22-92
COMPLETION TIME 9:30 (AM/PM) DATE 3-22-92
CEMENT COMPANY Allied