

11-14

1 040353

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,243-40-00
SW SE, SEC. 22, T 28 S, R 11 W/R
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5205
Operator: Mid Continent Energy Corporation
Name & Address 155 North Market, Suite 200
Wichita, KS 67202

Lease Name Brenton Well # 1-22
County Pratt 148.88
Well Total Depth 4581 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 484

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:15 a.m. Day: 14 Month: 11 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 4580' PBD 3324' Perfs at 2406-12, 2550-65' Elevation 1776' GL

1st plug build bridge to 2600', sand to 2350' with 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

RECEIVED

STATE CORPORATION COMMISSION Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging operations attended by Agent?: All X Part _____ None _____

Operations completed: Hour: 10 a.m. Day: 14 Month: 11 Year: 19 89
Wichita, Kansas

ACTUAL PLUGGING REPORT 1st plug built a bridge at 2600', sanded back to 2350' and dumped 5 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 800 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1817' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 12-6-89

INV. NO. 26644

Signed Stephen J. Pfeifer (TECHNICIAN)