

1 050437

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,058-00-00

NW NW NE, SEC. 15, T 28 S, R 13

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8483

Lease Name County Farm Well # 1

Operator: Rival Resources

County Pratt 149.67

Name & Address: 2727 Bryant, Suite 430

Well Total Depth 4605 feet

Denver, CO 80211

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 368

Abandoned Oil Well X Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Hembree Well Service, Inc. License Number 6907

Address Box 458, Ness City, KS 67560

Company to plug at: Hour: 10:00 am Day: 17 Month: January Year: 19 85

Plugging proposal received from Harvey Moore

(company name) Rival (phone) 303-893-9242

were: 4 1/2" set at 4507' Perfs at 3911-3912'

1st plug sand back to 3860' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 100 sx cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:30 am Day: 17 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3860' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 100 sx cement

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 450 psi and shut in 350 psi

JAN 23 1985

Remarks: Recovered 3300' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by CONSERVATION DIVISION
(If additional description is necessary, use BACK of this form.)

INVOICED

(if not) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 1-28-85

FEB 18 1985

INV. NO. 6698 1-17