

080049

7-7

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,858-00-00
SW NE NE, SEC. 15, T 28 S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 30043

4290 feet from S section line
990 feet from E section line

Lease Name County Farm Well # 1

Operator: Michael W. Kirkman (was Kachina Oil
Name & Co.)
Address Box 982
Pratt, KS 67124

County Pratt 149.50

Well Total Depth 4600 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 938

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 7 Month: 7 Year: 19 89

Plugging proposal received from Mike Kirkman

(company name) Michael W. Kirkman (phone) 316-672-7471

were: 4 1/2" at 4555' Perfs at 3884-90'

1st plug sand back to 3830' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 3 sx hulls, 50 sx cement, 10 sx gel, release 8 5/8" wiper plug and pump

100 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:05 p.m. Day: 7 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3830' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped 3 sx hulls, 50 sx cement, 10 sx gel, released 8 5/8" wiper plug and
pumped 100 sx cement.

Maximum pressure 550 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1989

7-11-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3200' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

DATE 7-13-89

Signed Mike Asain
(TECHNICIAN)

INV. NO. 25327