

10-18

15-151-20509-00-00

To: 1 040179
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA

C NE SE, SEC. 7, T 28 S, R 11 W/E

1980 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # none (landowner)

Lease Name Goven Well # 1

Operator: Corlis Goyen

County Pratt 82.71

Name & Address R #1

Well Total Depth 2545 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address Box 847, Pratt, KS, 67124

Company to plug at: Hour: 10:30 a.m. Day: 18 Month: 10 Year: 19 88

Plugging proposal received from Fred Mease

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 4 1/2" at 2606' Perfs at 2510-12'

1st plug pump 2 sx hulls and 20 sx cement,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1988
10-27-88
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 18 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 200 lbs. hulls and 20 sx common cement,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, 8 5/8" wiper plug and 100 sx cement.

Maximum pressure 600 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1579' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / observe this plugging.

DATE 10-31-88

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 22847

10-18

NOV 15 1988