

1 050516

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,555 -00-00
150' E & 50' N of
C SE NE , SEC. 7 , T 28 S, R 11 W/K

TECHNICIAN'S PLUGGING REPORT

3350 feet from S section line
1470 feet from E section line

Operator License # 5050

Lease Name Goyen Well # 2

Operator: Hummon Corporation
Name & Address: 400 One Main Place
Wichita, KS 67202

County Pratt

Well Total Depth 3070 9978 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 379

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:00 pm Day: 1 Month: May Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 2605' PBTD 2564' Perfs at 2508-2511'

1st plug sand back to 2460' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 100 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:00 pm Day: 1 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 2460' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 21 1985
5-21-85
CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 750 psi and shut in 500 psi

Remarks: Recovered 2000' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by B.J.-Titan
(If additional description is necessary, use BACK of this form.)

(xxx did not) observe this plugging.

INVOICED

DATE 5-21-85

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 8208