

To: 1051837  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-24

API NUMBER 15-119-20,929-00-00  
SW SW SE, SEC. 4, T. 32 S, R. 27 W/X  
330 feet from S section line  
2970 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30444  
Operator: Charter Production Company  
Name: 142 N. Mosley  
Address: Wichita, KS 67202

Lease Name Rempel Well # 1  
County Meade 189.86  
Well Total Depth 5842 feet  
Conductor Pipe: Size            feet  
Surface Casing: Size 8 5/8 feet 1504

Abandoned Oil Well            Gas Well            Input Well            SWD Well            D&A X

Other well as hereinafter indicated           

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 9 a.m. Day: 24 Month: 9 Year: 19 94

Plugging proposal received from Bill Craig

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

vers: to fill hole with heavy mud and spot cement through drill pipe  
1st plug at 1540' with 50 sx cement, 2nd plug at 600' with 40 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All            Part            None X

Operations Completed: Hour: 11:30 a.m. Day: 24 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 1540' with 50 sx cement,

2nd plug at 600' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

Did not observe this plugging.

DATE 10-6-94

INV. NO. 41321

Signed Richard M. Lacey  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 28 1994  
9-28-94

FOR REC USE:  
EFFECTIVE DATE: 9-14-94  
DISTRICT: 9  
COUNTY: Wichita

State of Kansas  
NOTICE OF INTENTION TO DRILL 119-20,929

Must be approved by the K.C.C. five (5) days prior to commencing well

Spud Date: 9 month 12 day 94 year

East 32 S. R. 27 West  
SW SW SE 4 Top

OPERATOR: License # 30444  
Name: Charter Production Company  
Address: 142 N. Mosley  
City/State/Zip: Wichita, KS 67202  
Contact Person: Jerald W. Rain  
Phone: 316/263-4906

330 feet from South / NORTH line of Section  
2970 feet from East / West line of Section  
IS SECTION X REGULAR        IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Menard  
Lease Name: Rempel Well #: 1  
Field Name: Wildcat

CONTRACTOR: License #: 5422  
Name: Abarcrombie

Is this a Prorated/Spaced Field? yes X no  
Target Formation(s): Chester  
Nearest lease or unit boundary: 330  
Ground Surface Elevation: 2515 feet MSL

Well Drilled For: Well Class: Type Equipment:  
Oil ... Enh Rec ... Infield ... Mud Rotary  
X Gas ... Storage ... Pool Ext. ... Air Rotary  
OHW ... Disposal ... Wildcat ... Cable  
Solaria: ... P. of Hole ... Other

Water well within one-quarter mile: yes X no  
Public water supply well within one mile: yes X no  
Depth to bottom of fresh water: 180'  
Depth to bottom of usable water: 260'

Operator: Abarcrombie  
Well Name:         
Comp. Date:        Old Total Depth:       

Surface Pipe by Alternate: X 1        2  
Length of Surface Pipe Planned to be set: (1500) 300'  
Length of Conductor Pipe required: NA  
Projected Total Depth: 5900'

Formation at Total Depth: Chester  
Water Source for Drilling Operations:  
X well        farm pond        other

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, true vertical depth:         
Bottom Hole Location:         
Exp. 3/9/95

Oil Permit #:         
Will Cores Be Taken? yes X no  
If yes, proposed zone:         
300' Alt. I Req.

**AFFIDAVIT**

Pusher Bill Rich  
SPUD DATE 9-12-94 INIT. DR  
LENGTH SURFACE PLANNED 1500'  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect.        bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE         
SURFACE PIPE 3 1/2" @ 1504 CONDUCTOR         
ANHYDRITE T- B ELEVATION         
TD 5842 FORMATION         
RAN PIPE @        DV TOOL        ALT II DONE         
       SX        SX        Y        N         
       Arbuckle Plug @        Ft. W/        SX  
       Hug./Council @        Ft. W/        SX  
       Anhydrite Base @ 40 Ft. W/ 50 SX  
       1/2 Base Anhyd. @ 600 Ft. W/ 40 SX  
       1/2, 1/2 Plug @        Ft. W/        SX  
       Bottom Surface @        Ft. W/        SX  
       40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 1 1/2 SX MOUSE HOLE W/ 10 SX  
WATER WELL        SX (I) Well        Pond         
TECHNICIAN A. L. [unclear] DATE 9-23-94 Hauling         
TYPE OF CEMENT 60/40 per 6% grt  
STARTING TIME 9:00 AM DATE         
COMPLETION TIME 11:30 AM DATE 9-24-94  
CEMENT COMPANY allied