

To: B 1 090616.
STATE CORPORATION COMMISSION
Wichita State Office Bldg. 10-30 PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5152
Operator: Lee Banks d/b/a Banks Oil Co.
Name & Address 200 W. Douglas, Ste. 550
Wichita, KS 67202

API NUMBER 15- 119-20,292-00-00
C SW SW, SEC. 6, T 32 S, R 27 W/E
660 feet from S section line
4620 feet from E section line
Lease Name Cornelsen B Well # 1
County Meade 179.40
Well Total Depth 5520 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1423

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151
Address: Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 1 p.m. Day: 30 Month: 10 Year: 1995

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

Work: 4 1/2" at 5519' w/150 sx cement, PBDT 5463'; Perfs at 5412'
1st plug pump 20 sx cement and 2 sx hulls to bottom,
2nd plug at 1450' with 50 sx cement,
3rd plug at 700' with 40 sx cement,
4th plug at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV - 1 1995
CONSULTANT
WICHITA, KANSAS

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 30 Month: 10 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement with 2 sx hulls over perfs,
2nd plug pulled casing to 1450' and spotted 50 sx cement,
3rd plug pulled to 700' and spotted 40 sx cement,
4th plug pulled to 40' and pumped 10 sx cement. Kept hole loaded with mud to balance plugs.

Remarks: Used common cement by Sargent & Horton. Recovered 2300' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-3-95
INV. NO. 43930

Signed [Signature]
(TECHNICIAN)