

1031512

TO: STATE CORPORATION COMMISSION

API NUMBER 15-119-20,996.00-00
S2 S/2 SE SEC. 17, T 32 S, R 27 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME FRIESEN WELL # 1-17

TECHNICIAN'S PLUGGING REPORT COUNTY MEADE 186.06

OPERATOR LICENSE # 06113 WELL TOTAL DEPTH 5725 FEET

OPERATOR: LANDMARK ENERGY EXPL. PRODUCTION CSG: SIZE " FEET

NAME AND 1861 NORTH ROCK ROAD SURFACE CASING: SIZE 8 5/8" @ 1564' WITH SX

ADDRESS WICHITA, KS 67206

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ABERCROMBIE RTD LICENSE NUMBER 30684

ADDRESS 150 N MAIN, STE 801, WICHITA, KS 67202-1383

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 11 MONTH: 01 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM BILL CRAIG

(COMPANY NAME) ABERCROMBIE RTD (PHONE) 316-262-1841

WERE:

1ST PLUG AT 1590' WITH 50 SX CEMENT. 2ND PLUG AT 600' WITH 40 SX CEMENT.

3RD PLUG AT 40-0' WITH 10 SX CEMENT.

4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 1:15 PM DAY: 11 MONTH: 01 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1590' WITH 50 SX CEMENT. 2ND PLUG AT 600' WITH 40 SX CEMENT.

3RD PLUG AT 40-0' WITH 10 SX CEMENT.

4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED Steve Durrant (TECHNICIAN) FORM CP-2/3

STATE CORPORATION COMMISSION

JAN 14 1999

1-14-99 CONSERVATION DIVISION

1-15-99 60553