

1 020348

15-119-10169-00-790

149 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19- Drilled 3/30/60

App. NE SW SW, SEC. 34, T 32 S, R 27 W/E

1250 feet from S section line

4030 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9183

Lease Name Reimer Well # 1

Operator: Bentley & Laing

County Meade 186.87

Name & Address P.O. Box 294

Well Total Depth 5750 feet

Wichita Falls, TX 76307

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 9 5/8 feet 1543

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address P.O. Box 596, Liberal, KS 67905-0596

Company to plug at: Hour: 3:45 p.m. Day: 16 Month: 1 Year: 19 91

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 4 1/2" at 5748', Perfs at 5628-36'

1st plug pump 1 sx hulls and 25 sx cement,

2nd plug pump 50 sx cement at 1570', displace with mud,

3rd plug pump 50 sx cement at 650', displace with mud,

4th plug pump 15 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 19 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perfs, pressured to 300#, displaced with mud,

JAN 31 1991  
1-31-91

2nd plug pumped 50 sx cement at 1570', displaced with mud,

3rd plug pumped 50 sx cement at 650', displaced with mud,

4th plug pumped 15 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 2403' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED (10) observe this plugging.

DATE 2-11-91

Signed Glenn Barlow  
(TECHNICIAN)

INV. NO. 30637