

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-20,555 ⁰⁰⁻⁰⁰

LEASE NAME Goyen

WELL NUMBER 2

50' N Ft. from S Section Line
C-SE-NE

150' E Ft. from E Section Line

SEC. 7 TWP. 28S RGE. 11 ~~XXXX~~ (W)

COUNTY Pratt

Date Well Completed 10/21/78

Plugging Commenced 4/18/85

Plugging Completed 5/1/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hummon Corp.

ADDRESS 400 One Main Place, Wichita, KS 67202

PHONE# (316) 263-8521 OPERATORS LICENSE NO. 5050

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City (Lacy)

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3070

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	379	None
				4 1/2	2605	2000

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Plug back at 2564, sand from 2564 to 2455, 4sx cement with dump bailer, Sun pump in 3sx hulls, 15sx jell, 50sx cement, 10sx jell 1sx hulls, 100sx cement. 60.40 poz - 2%cc pump MAS 750 Shut in 500

John Swinford on location

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corp. License No. RECEIVED

STATE CORPORATION COMMISSION

Address P.O. Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Elmo Morgenstern (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

MAY 14 1985
5-14-85
CONSERVATION DIVISION
Wichita, Kansas

CAREN J. McCULLOUGH

NOTARY PUBLIC

STATE OF KANSAS

My Appt. Exp. 6-29-87

(Signature) Elmo Morgenstern

(Address) _____

SUBSCRIBED AND SWORN TO before me this 9th day of May, 19 85

My Commission Expires: June 29, 1987

Hummon Oil Company - Goyen #2
Approx. C SE NE Sec. 7-28S-11W
Pratt County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: October 15, 1978
Completed: October 21, 1978

Drillers Log

Sand	160
Red Bed	1015
Shale	1308
Anhydrite	1318
Shale & Shells	1515
Shale	1820
Shale & Shells	2220
Lime	2395
Shale & Shells	2505
Shale & Lime	2805
Lime	2965
Lime & Shale	3070 RTD

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1985

CONSERVATION DIVISION
Wichita, Kansas