

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2125
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20,292-00-00

LEASE NAME Cornelson B

WELL NUMBER 1

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 6 TWP. 32 RGE. 27 or (W)

COUNTY Meade

Date Well Completed 12-12-77

Plugging Commenced 10-27-95

Plugging Completed 10-30-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Banks Oil Co.

ADDRESS 200 West Douglas, Suite 550, Wichita, Ks. 67202

PHONE# (316) 267-0783 OPERATORS LICENSE NO. 05152

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-26-95 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Morrow Depth to Top 5412 Bottom 5417 R.T.D. 5520

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow		1423	0	8 5/8"		
		5519	0	4 1/2"		

NOV 14 1995

11-14-95

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s Mixed 2 5x hulls & 20 5x cmt. to plug perfs from 5412 to 5212. Recovered 2300 ft 4 1/2. Mixed 50 5x cmt. @ bottom of 8 5/8" from 1450 to 1300. Mixed 40 5x plug from 700 to 600. Mixed 10 5x plug from 40 to 0. Cut off & capped 8 5/8" 3 ft. below ground level. Used mud between all plugs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Banks Oil Co.

STATE OF Kansas COUNTY OF Sedgwick, ss.


Lee Banks (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Lee Banks

(Address) 200 W. Douglas, Suite 550 ..
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 10 day of November, 19 95



My Commission Expires: Aug. 28, 1996

Darlene J. May
Notary Public