

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-119-20996 0000

LEASE NAME Friesen

WELL NUMBER 1-17

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

330 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 17 TWP. 32S RGE. 27 (E) or (W)

LEASE OPERATOR Landmark Energy Expl.

COUNTY Meade

ADDRESS 1861 N Rock Road, #205, Wichita, KS 67206

Date Well Completed 1-11-99

PHONE# (316) 634-1363 OPERATORS LICENSE NO. 06113

Plugging Commenced 1-11-99

Character of Well D/A

Plugging Completed 1-11-99

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-11-99 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Enclosed If not, is well log attached?

Producing Formation NONE Depth to Top  Bottom  T.D. 5720

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
KANSAS CORPORATION COMMISSION  
1-19-99  
JAN 19 1999

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	1564	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Filled with heavy mud. 1st plug @ 1590' cemented w/50 sks, 2nd plug @ 600' cemented w/40 sks, 3rd plug @ 40' cemented w/10 sks, 15' sks in rathole, 10' sks mouse hole. Total of 125 sks 60/40 poz, 6% gel.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: LANDMARK ENERGY EXPLORATION INC.

STATE OF Kansas COUNTY OF Sedgwick, ss.

CRAIG L. CAULK (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig L. Caulk

(Address) 1861 N. Rock Road Ste 205

SUBSCRIBED AND SWORN TO before me this 19th day of January, 19 99

Deborah K. Autry  
Notary Public

