

15-119-10169-00-00

LEASE NAME Reimer

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1250 Ft. from S Section Line

1250 Ft. from E Section Line

SEC. 34 TWP. 32S RGE. 27W (E) or (W)

COUNTY Meade

LEASE OPERATOR Bentley S Laing

Date Well Completed 03/30/60

ADDRESS P.O.Box 294 Wichita Falls, Texas 76307

Plugging Commenced 1-16-91

PHONE (817) 723-5001 OPERATORS LICENSE NO. 9183

Plugging Completed 1-21-91

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Glenn Barlow

Is ACO-1 filled? If not, is well log attached?

Producing Formation Morrow Sand Depth to Top 5628 Bottom 5636 T.D. 5750

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION
2-25-91
FEB 25 1991

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Gas	5628	5636	9 5/8 4 1/2	1543 5748	0 2403

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 25 sks. of cement & 1 sk. of hulls from 5636 to 5400

Pump 50 sks. of cement from 1580 to 1480

Pump 50 sks. of cement from 650 to 550

Put 15 sks. of cement from 40 to 0 Cut off & cap 9 5/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O.Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

Doyle Bentley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Doyle Bentley

(Address) P. O. Box 294, Wichita Falls, TX 76307



Subscribed and sworn to before me this 22 day of February, 19 91

Gloria A. Spreng
Notary Public

My Commission Expires: 07/18/94